

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

SEE INSTRUCTIONS IN HOW TO COMPLETE NATIONAL REGISTER FORMS
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC

Trinity Episcopal Church

AND/OR COMMON

2 LOCATION

STREET & NUMBER

409 North Liberty

CITY, TOWN

Independence

VICINITY OF

STATE

Missouri

CODE

29

NOT FOR PUBLICATION

CONGRESSIONAL DISTRICT

#4 - Hon. Ike Skelton

COUNTY

Jackson

CODE

95

3 CLASSIFICATION

CATEGORY

DISTRICT

X BUILDING(S)

STRUCTURE

SITE

OBJECT

OWNERSHIP

PUBLIC

X PRIVATE

BOTH

PUBLIC ACQUISITION

IN PROCESS

BEING CONSIDERED

STATUS

X OCCUPIED

UNOCCUPIED

WORK IN PROGRESS

ACCESSIBLE

X YES: RESTRICTED

YES: UNRESTRICTED

NO

PRESENT USE

AGRICULTURE

COMMERCIAL

EDUCATIONAL

ENTERTAINMENT

GOVERNMENT

INDUSTRIAL

MILITARY

MUSEUM

PARK

PRIVATE RESIDENCE

X RELIGIOUS

SCIENTIFIC

TRANSPORTATION

OTHER:

4 OWNER OF PROPERTY

NAME

Trinity Episcopal Church Parish

STREET & NUMBER

409 North Liberty

CITY, TOWN

Independence

VICINITY OF

STATE

Missouri 64050

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC.

Recorder of Deeds, Jackson County Courthouse Annex

STREET & NUMBER

308 West Kansas

CITY, TOWN

Independence

STATE

Missouri 64050

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

1. Independence, Missouri

DATE

1978

FEDERAL STATE COUNTY X LOCAL

DEPOSITORY FOR
SURVEY RECORDS

published: Independence, Mo.: Independence Press

CITY, TOWN

STATE

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

TRINITY EPISCOPAL CHURCH

CONTINUATION SHEET

ITEM NUMBER 6 PAGE 1

2. Missouri State Historical Survey
1978 state
Department of Natural Resources
P.O. Box 176
Jefferson City, Missouri 65102

ITEM NUMBER 11 PAGE 1

2. Claire F. Blackwell, Editor
Department of Natural Resources
P.O. Box 176 314/751-4096
Jefferson City, Missouri 65102

DESCRIPTION

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Trinity Episcopal Church, 409 North Liberty, Independence, Missouri, is a red brick, gable-roofed structure. Built ca. 1881-1884, it has the simplicity and form of Early English Gothic parish church prototypes. Small in scale, it consists of a rectangular nave facing west, a square chancel on the east, and a rectangular organ chamber on the south. Although the addition of a parish hall and entranceway ca. 1959 has largely obscured the organ chamber and chancel on the exterior, the simple interior, highlighted by handsome exposed trusswork, has been little changed.

EXTERIOR

The church is constructed of red brick on a foundation of uncoursed rubble. The brick is laid in stretcher bond on the primary (western) facade and in common bond on the secondary facades. Smoothed cut stone is employed decoratively for copings and weathering surfaces. Lancet windows of the nave are trimmed with cut stone lintels and pointed arches of double rows of headers; simple architrave surrounds painted maroon frame the openings. Asphalt shingles cover the gable roofs of all sections of the church.

The plan of Trinity is basically rectangular. A five-bay nave is oriented east-west. On the east end of the nave is located a square chancel and on the south side an organ chamber is positioned perpendicular to the nave. A gable-roofed entrance porch is centered on the western facade.

Overall dimensions of the original building were approximately 72' east-west by 40' north-south. Exact measurements are difficult to determine precisely, as parts of the original plan have been removed or obscured by additions. Overall dimensions of the entire structure, that is including the parish hall and entranceway, are approximately 150' east-west by 50' north-south.

The primary facade of Trinity is oriented to the west. The facade wall rises from a firmly buttressed base, tapers along the rake of the roof, and terminates in a bell cote which masks the gable peak behind. Smoothed cut stone caps the angles of the buttresses, forms the coping at the roof line, and trims the bell cote. A gabled entrance porch is centered on this facade, and above it a stained glass, oculus window pierces the wall.

The main entrance, centered on the entrance porch, is ornamented by a semicircular, glazed fanlight. Radiating wrought iron muntins divide the field into eight lights. The door, a replacement of the original, double-leaf, ten-panel door, is a double-leaf, wooden door with wrought iron handles.

The five bays of the northern facade are articulated by attached wall buttresses and pierced by lancet windows. The lancet windows are capped by pointed arches of double rows of headers and filled with a geometric pattern of lozenges below and with an abstract curvilinear design in the arch field.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

TRINITY EPISCOPAL CHURCH

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 1

The southern facade originally had three bays, but has been reduced to two with the addition of the gabled entranceway on the south. The south organ chamber has been almost completely lost by the addition of that entranceway. The only vestige of the chamber is its gabled roof, which peeks forlornly through the roof of the new entranceway.

The east chancel has also been obscured, for the new parish hall was built directly onto the eastern end of the church, blocking the triple lancet window which originally lit the interior sanctuary.

There are three entranceways to the church other than the main entrance previously mentioned: one on the west side of the added entranceway on the south; one on the south, approached by a flight of steps down, which leads to the basement; and one on the south side of the added parish hall. Originally only two doorways existed, the main door on the western facade and another on the east side of the organ chamber.

INTERIOR

The nave of the church is a rectangular, five-bay chamber. Simple wooden pews face east, flanking a center aisle. The forward progression of the nave is interrupted by the position of the organ chamber at a right angle on the south. Opposite that chamber, pews of the choir are also arranged perpendicular to the nave, facing the organ.

A wall with a large arched opening defines the chancel behind. Three broad steps approach the chancel rail; another leads up to the chancel, where the altar rests on a footpace. The chancel is lit from the east by a triple lancet window. Blocked from sunlight by the parish hall behind, the windows are now lit artificially.

Accentuating the steeply pointed ceilings of nave, chancel and organ chamber is exposed trusswork of arch-braced form. Constructed of beams of stained and varnished walnut, the trusswork lends a mellow richness to an otherwise severely plain interior.

Nave walls are painted pale beige and the ceiling light green; in the chancel the walls are green and the ceiling beige. The well worn oak flooring of the nave is covered with bluish-green carpeting in aisle areas, and the entire chancel floor is carpeted. The pews are painted beige with contrasting dark brown trim; the socles are dark brown; and the windowsills, once dark brown, are now painted beige.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

TRINITY EPISCOPAL CHURCH

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 2

ALTERATIONS

1888 - The first organ was installed in Trinity Episcopal.¹

1890 - Stained glass windows were donated by Old St. Mary's Episcopal Church of Kansas City.² Records of the church do not specify what filled the windows before that donation.

1929 - Extensive remodelling was done in 1929, involving the excavation of a basement under the church. The basement was built large enough to contain Sunday School rooms, a guild room and a kitchen.³

1937 - Donation of a single stained glass window by Major William Bland. The window, which bears the donor's name, was originally in St. Mark's Episcopal Church in Kansas City.⁴

1938 - The original organ was removed and the present model installed. The pipes of the original organ were retained as a decorative screen.⁵

1958-1959 - The most drastic changes, including those affecting the exterior form of the church, were made at this time. A two-story, brick parish hall and a one-story, brick entranceway, designed by William Fullerton, were added. The parish hall was built directly onto the church on the east end of the chancel. As this blocked the chancel windows, artificial lighting was installed behind.

The entrance hall was built onto the south facade, providing entrance to the parish hall behind and to the organ chamber to the north. This addition involved the removal of the actual walls of the organ chamber. The two lancet windows and one oculus window from the south end were salvaged and are presently stored in the church basement. Addition of the entranceway also affected the south side of the nave, reducing it from three to two bays.

Photographic documentation provides evidence that the interior of the organ chamber was altered as well. A pre-alteration photograph shows the chamber closed off from the nave by a wall. Two arched doorways pierce the wall, and the original organ pipes are centered decoratively on the wall above. In addition arched openings occurred above the doorways, admitting the southern light from the end windows of the organ chamber into the nave.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

TRINITY EPISCOPAL CHURCH

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 3

SITE

Trinity is located about two blocks north of the old Independence Square in downtown Independence and approximately three blocks east of the Harry S. Truman Historic District. The building faces west across Liberty Street, looking toward another church on the opposite side. Directly south is a gravestone company, and due north is the parking lot of an adjoining apartment complex.

CONDITION AND USE

Trinity Episcopal Church is presently in good condition. Regular attention is given to maintenance and restoration of the building. But for the "modernizations" which resulted in the alterations of the church's original exterior form, care has been taken to maintain the building's original integrity. It is still used regularly for church services and is respected by members of the community as part of their local heritage.

FOOTNOTES

1. "Trinity Pipe Organ, Oldest in City in Finale Sunday," The Independence Examiner, May 27, 1938.
2. Lucille Grumman, "History of Trinity Episcopal Church," Independence, Mo., p. 3.
3. "To Remodel a Church," The Independence Examiner, December 11, 1929.
4. "Dedicate a Memorial," The Independence Examiner, January 25, 1937.
5. "Trinity Pipe Organ," The Independence Examiner, May 27, 1938.

8 SIGNIFICANCE

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input checked="" type="checkbox"/> RELIGION	
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE	
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE	
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER	
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION	
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input checked="" type="checkbox"/> OTHER (SPECIFY: Association with Truman Family)	
		<input type="checkbox"/> INVENTION			

SPECIFIC DATES ca. 1881-1884 BUILDER/ARCHITECT John Hubbard Sturgis

STATEMENT OF SIGNIFICANCE

Trinity Episcopal Church, 409 North Liberty, Independence, Missouri, is significant as the earliest organized Episcopal parish in the Jackson County area and is important in the development of the Episcopal Church in western Missouri. Designed by noted Boston architect John Hubbard Sturgis, Trinity is a unique example of his work in the Midwest and an unusual Victorian era example of the parish church type popular in the early Gothic Revival of the 1840's and 50's. In addition, Trinity Episcopal was the site of the marriage of Elizabeth Virginia Wallace and Harry S. Truman, as well as numerous other events in the life of the Truman family.

The first Episcopal service held in Independence, Missouri, was performed in 1837 by the Right Reverend Jackson Kemper, but it was not until 1843 that regular services were conducted.¹ The Trinity Church congregation was organized in 1844, the earliest in the area, and thus Trinity became the "mother church" of outlying areas, including Kansas City.² When Trinity was officially admitted to the Episcopal diocese as the first parish in Jackson County in 1855, it did not yet possess a church of its own.³ Finally, in November, 1877, a lot was purchased at 114 South Main, and by November of 1878 a small wooden church had been built.⁴ Less than two years later, on April 18, 1880, this first church was destroyed by a tornado.


A cyclone on April 18th destroyed Marshfield and other places, causing appalling loss of life and demolished Trinity Church, Independence, which had not been finished long. Nor had it been paid for fully. The rector's daughter raised \$400.00 the next day for a new building in Independence.⁵

On March 5, 1881, after two fund-raising trips to the East, Trinity's pastor, the Reverend John Dunn, presented to the vestry plans for a new church by the architect John Hubbard Sturgis of Boston.⁶ The building of this church took place from 1881-1884, and Trinity Episcopal Church was consecrated on October 1, 1891.⁷

John Hubbard Sturgis (1834-1888) was a partner in the prominent Boston, Massachusetts architectural firm of Sturgis and Brigham. For many years the president of the prestigious Boston Society of Architects, Sturgis was a well-travelled architect who divided his time between Boston and London. Some of his works include the old Boston Museum of Fine Arts (1870-76; destroyed in 1906), the Edward N. Perkins House in Boston (1868-69), and the Church of the Advent in Boston (1878-83).⁸ To date the only building attributed to Sturgis west of Massachusetts is Trinity Episcopal Church in Independence, Missouri.⁹

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**



TRINITY EPISCOPAL CHURCH

CONTINUATION SHEET

ITEM NUMBER 8 PAGE 1

It is not known why such a prominent Eastern architect would have been selected to design a church for this small, rather impoverished parish in Missouri. One possible conjecture is that the plight of Trinity, that is the loss of the early frame church in a tornado, came to the attention of Sturgis during one of Reverend Dunn's fund-raising trips East. However, no concrete reasons have been recorded.

Although the original plans for Trinity are no longer extant, vestry minutes indicate the specifications of the Sturgis design were closely followed. The only major change in the design seems to have been the substitution of brick for the stone specified by Sturgis.¹⁰ In the light of the relative poverty of the parish, this was undoubtedly an economic decision.

Interestingly enough, Sturgis' eastern works have little in common with Trinity Episcopal. Although Sturgis was most definitely a practitioner of the Gothic mode, his taste led to the more elaborate Victorian interpretations of that style. His most famous work, the old Boston Museum of Fine Arts,¹¹ was a thoroughgoing essay in High Victorian, Italianate Gothic, while Trinity Episcopal has the simplicity of design and plan of the Early Gothic Revival. Again, we can only speculate as to the reasons for this stylistic anachronism. However, the financial state of the Trinity parish must have figured in. The parish church type provided an eminently suitable vehicle of expression for the Episcopal faith,¹² while the simplicity of its form allowed for the minimization of construction costs.¹³

Whatever the reasons behind the choice of Sturgis as architect and his selection of the provincial, Early English Gothic type, the results are pleasing. Though extremely simple in form and minimal in decoration, Trinity has a grace born of this simplicity. Reflecting the form of parish churches of the Early Gothic Revival, (which were inspired by medieval English parish churches),¹⁴ Trinity has a small rectangular nave, with an expressed chancel on the eastern end and an organ chamber projecting from the south. Highlighted by a simple bell cote on the primary (western) facade, the long sides of the building are accentuated by the regular rhythm of alternating lancet windows and attached wall buttresses. The interior is of equal simplicity, but enriched by exposed walnut trusswork of arch-braced form. The resulting building provides an aesthetically rewarding expression of the Early Gothic type for what was originally a poor Episcopal church in a small town environment.

The third area of Trinity's significance is in its association with the Truman family. Trinity Episcopal was the parish church of Elizabeth Virginia Wallace.¹⁵ There on June 28, 1919, Elizabeth married Harry S. Truman. The eventual election of Harry S. Truman to the Presidency of the United States brought to Trinity a place in the presidential history of the United States.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

TRINITY EPISCOPAL CHURCH

CONTINUATION SHEET

ITEM NUMBER 8 PAGE 2

The Truman family events which occurred in Trinity Episcopal Church took place before and after Harry Truman's terms as President. In addition to his wedding, these events included his daughter Margaret's marriage to Clifton Daniel on April 21, 1956, and the christening of Margaret's children.

The survey of Missouri's historic sites is based on the selection of sites as they relate to theme studies outlined in "Missouri's State Historic Preservation Plan." Accordingly, Trinity Episcopal Church is being nominated to the National Register of Historic Places as an example of the themes of "Religion," and "Architecture."

FOOTNOTES

1. C.B.F. van Alstyne Welles, A Documentary History of the Episcopal Church in West Missouri (Chillicothe, Mo.: The Community Press, 1964), pp. 15, 282.
2. Ibid., p. 22; "Little Brick Church Housing Episcopalians Built in 1881," The Independence Examiner, October 9, 1943.
3. Welles, A Documentary History, p. 38.
4. Lucille Grumman, "History of Trinity Episcopal Church", Independence, Mo., p. 1.
5. Welles, A Documentary History, p. 81.
6. Trinity Episcopal Church, Vestry Minutes, March 5, 1881.
7. Welles, A Documentary History, p. 121.
8. For information on John Hubbard Sturgis see: Margaret Henderson Floyd, "A Terra-Cotta Cornerstone for Copley Square: Museum of Fine Arts, Boston, 1870-1876", Society of Architectural Historians Journal 32 (May, 1973); 83-103.
9. Sturgis seems to have confined his practice to the East. However, he is mentioned in the Vestry Minutes, 1878-1883, as the architect of Trinity Episcopal Church. The minutes further record minimal payments to Sturgis, although the records are not clear as to the total amount paid.
10. Trinity Episcopal Parish, Vestry Minutes, May 28, 1881.
11. The old Museum of Fine Arts, Boston, is discussed at length by Floyd in "A Terra-Cotta Cornerstone for Copley Square."

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

TRINITY EPISCOPAL CHURCH

CONTINUATION SHEET

ITEM NUMBER 8 PAGE 3

12. The suitability of the parish church type for the Episcopalian denomination was firmly established in the period of the Early Gothic Revival. See Phoebe B. Stanton, The Gothic Revival & American Church Architecture: An Episode in Taste, 1840-1856 (Baltimore: The Johns Hopkins Press, 1964), p. 4.
13. Vestry Minutes of the Trinity Episcopal Parish, dated April 10, 1882, indicate an amount of \$252.02 owed to William M. Randall, bricklayer.
14. The parish church type and its expression in the Early Gothic Revival in America is discussed by Stanton in The Gothic Revival and American Church Architecture.
15. George Sessions Perry, "Independence, Missouri", The Saturday Evening Post, September 2, 1950, p.23.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

1. "City's Churches Date Back to Earliest Days," The Independence Examiner, March 31, 1962.
2. "Dedicate a Memorial," The Independence Examiner, January 25, 1937.

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY approximately 1/7 acre

QUADRANGLE NAME "Independence, Mo."

QUADRANGLE SCALE 1:24,000

UTM REFERENCES

A 15 377500 4328040

B

C

D

E

F

G

H

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE CODE COUNTY CODE

STATE CODE COUNTY CODE

11 FORM PREPARED BY

NAME / TITLE

1. Sarah Schmittlein

ORGANIZATION

Historic Kansas City Foundation

DATE

April 10, 1978

STREET & NUMBER

5025 Troost #2N

TELEPHONE

816/523-4548

CITY OR TOWN

Kansas City

STATE

Missouri 64110

12 STATE HISTORIC PRESERVATION OFFICER CERTIFICATION

THE EVALUATED SIGNIFICANCE OF THIS PROPERTY WITHIN THE STATE IS:

NATIONAL

STATE X

LOCAL

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

STATE HISTORIC PRESERVATION OFFICER SIGNATURE

TITLE

Director, Department of Natural Resources and
State Historic Preservation Officer

DATE

FOR NPS USE ONLY

I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER

DATE

ATTEST:

KEEPER OF THE NATIONAL REGISTER

DATE

CHIEF OF REGISTRATION

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

TRINITY EPISCOPAL CHURCH

CONTINUATION SHEET

ITEM NUMBER 9 PAGE 1

3. Floyd, Margaret Henderson. "A Terra-Cotta Cornerstone for Copley Square: Museum of Fine Arts, Boston, 1870-1876," Society of Architectural Historians Journal 32 (May, 1973): 83-103.
4. Grumman, Lucille. "History of Trinity Episcopal Church," Independence, Mo.
5. Independence, Missouri Centennial 1827-1927. Independence, Mo.: Independence Centennial Association, 1927.
6. Independence, Mo. Trinity Episcopal Church, Vestry Minutes, 1878-1883.
7. "Interior of Old Trinity Church is Given a Thorough Renovating," The Independence Examiner, February 10, 1950.
8. "Little Brick Church Housing Episcopalians Built in 1881," The Independence Examiner, October 9, 1943.
9. "New Episcopal Chapel Planned," The Independence Examiner, May 22, 1956.
10. Perry, George Sessions. "Independence, Missouri." The Saturday Evening Post, September 2, 1950, pp. 22-24, 70-74.
11. Stanton, Phoebe B. The Gothic Revival and American Church Architecture: An Episode in Taste 1840-1856. Baltimore; The Johns Hopkins Press, 1968.
12. "To Remodel a Church," The Independence Examiner, December 11, 1929.
13. "Trinity Pipe Organ, Oldest in City in Finale Sunday," The Independence Examiner, May 27, 1938.
14. Welles, C.B.F. van Alstyne. A Documentary History of the Episcopal Church in West Missouri. Chillicothe, Mo.: The Community Press, 1964.
15. Wuonola, Mark A. Church of the Advent Boston: A Guidebook. Boston: Thomas Todd Company, 1975.


71° 2' 11" NE
MISSOURI CITY

INDEPENDENCE QUADRANGLE

MISSOURI

7.5 MINUTE SERIES (TOPOGRAPHIC)

94° 22' 30"
39° 07' 30"



TRINITY EPISCOPAL CHURCH
U.S.G.S. 7.5' Quadrangle
"Independence, Mo." (1964, photorevised
1970 and 1974)

Scale: 1:24,000

UTM References: 15/377500/4328040

TRINITY EPISCOPAL CHURCH

COUNTY:

Jackson

LOCATION:

409 North Liberty
Independence
Trinity Episcopal Church Parish
409 North Liberty
Independence

OWNER:
ADDRESS:

DATE APPROVED BY A.C.:

October 27, 1978

DATE SENT TO D.C.:

February 9, 1979

DATE OF REC. IN D.C.:

February 23, 1979

DATE PLACED ON NATIONAL REGISTER:

April 27, 1979

DATE CERTIFICATE AWARDED
(AND PRESENTOR):

Given to Stuart Hutchison: July 12, 1983
Presented: October 4, 1983

DATE FILE REVIEWED:

Trinity Episcopal Church, 409 North Liberty, Independence, Missouri, is significant as the earliest organized Episcopal parish in the Jackson County area and is important in the development of the Episcopal Church in western Missouri. Designed by noted Boston architect John Hubbard Sturgis, Trinity is a unique example of his work in the Midwest and an unusual Victorian era example of the parish church type popular in the early Gothic Revival of the 1840's and 50's. In addition, Trinity Episcopal was the site of the marriage of Elizabeth Virginia Wallace and Harry S. Truman, as well as numerous other events in the life of the Truman family.

Trinity Episcopal Church, Independence,
Mo. Exterior view of west facade and
additions. Photo taken from the west
side of North Liberty Street looking
east.

TRINITY EPISCOPAL CHURCH #1
Independence, Missouri
Photographer: Sarah Schmittlein
1978

Neg. Loc.: C/O Sarah Schmittlein
5025 Troost #2N
Kansas City, Mo. 64110


Primary facade, view from southwest, showing
1959 additions.



Trinity Episcopal Church, Independence,
Mo. Exterior view of west facade entry
porch with fanlight window and 2-panel
double doorway

TRINITY EPISCOPAL CHURCH #2
Independence, Missouri
Photographer: Sarah Schmittlein
1978
Neg. Loc.: C/O Sarah Schmittlein
5025 Troost # 2N
Kansas City, Mo. 64110

Detail, primary facade. View from west.



Trinity Episcopal Church, Independence,
Mo. Exterior view of north facade of
church showing attached buttresses.
Photo taken from adjacent parking lot.

#3

TRINITY EPISCOPAL CHURCH
Independence, Missouri
Photographer: Sarah Schmidtlein
1978

Neg. Loc. C/O Sarah Schmidtlein
5025 Troost # 2N
Kansas City, Missouri 64110


Detail, north facade. View from northwest.



Trinity Episcopal Church, Independence,
Mo. Exterior view of one chancel win-
dow showing diamond pane leaded glass,
smooth stone sill and header bond brick
above window. Photo of south facade.

TRINITY EPISCOPAL CHURCH #4
Independence, Missouri
Photographer: Sarah Schmidtlein
1978
Neg. Loc.: C/O Sarah Schmidtlein
5025 Troost # 2N
Kansas City, Mo. 64110

Detail, lancet window of south facade.
View from south.



Trinity Episcopal Church, Independence,
Mo. Interior view of hammer-beam trusses
and diagonal sheathing in the nave.
Photo taken from chancel looking west.

TRINITY EPISCOPAL CHURCH #5
Independence, Missouri
Photographer: Sarah Schmidtlein
1978
Neg. Loc.: C/O Sarah Schmidtlein
5025 Troost # 2N
Kansas City, Mo. 64110

Interior trusswork. View from east.

026



Trinity Episcopal Church, Independence, Mo. Early exterior view of west facade showing exposed south transept and a small lean-to on the east of the transept. The 1959 south hallway addition


hid the transept walls. In 1959 the lean-to was also removed. The original 10-panel double door can be seen on the west entry porch.

Photo from Truman Library Collection -
Original ownership of photo The Kansas City Star.

TRINITY EPISCOPAL CHURCH #6
Independence, Missouri
Photographer: Unknown (Kansas City Star)

Neg. Loc.: Harry S. Truman Library & Museum,
Independence, Mo. 64050

View from southwest, before alterations of
1959, showing organ chamber intact.



TRINITY EPISCOPAL CHURCH
Independence, Missouri
Photographer: Harry Barth
April 1958

#7

Copy Neg. Loc.: Dept. of Natural Resources,
P.O. Box 176, Jefferson City, Missouri 65102

Interior, looking east toward chancel, before
renovations of 1959.



TRINITY EPISCOPAL CHURCH

#8

Independence, Missouri

Photographer: Harry Barth

1959

Copy Neg. Loc.: Dept. of Natural Resources,
P.O. Box 176, Jefferson City, Mo. 65102

Interior, looking south toward organ chamber,
after renovations of 1959.

